

		ITEM LIST	
ITEM	PART No.	DESCRIPTION	
1	GOLIFT-450	GOLIFT 450 CEILING HOIST	
2	PR8582L	PREMIUM 200 NURSING BENCH	
3	PR2050	PREMIUM ERGONOMIC BASIN	
4	PR4951	PREMIUM BASIN BRACKET	
5	N3897	CONTOUR 21 WC	
6	PR3600850	PLUS SUPPORT ARMS	
7	31272C	PREMIUM GRAB HANDLES	
8	RFW165	WALL MOUNTED PRIVACY SCREEN	
9	N7915	AIRBOX V2 HAND DRYER	
10	V6104	hand towel dispenser	
11	V6102	COUCH ROLL DISPENSER	
12	A9300	COLOSTOMY SHELF	
13	N3938	CLINICAL WASTE BIN	
14	N5160	GENERAL WASTE BIN	
15	V6111	XL TOUGH COAT HOOKS	
16	N5953	SAFETY MIRROR 1500x600	
17	N3987	MIRA SELECT FLEX SHOWER	
18	BY OTHERS	EMERGENCY CALL RESET POINT	
19	BY OTHERS	EMERGENCY PULL CORD	

## Notes:

- 1. ALL DIMENSIONS ARE IN MM.
- 2. FUSED SPURS, PLUMBING FIRST FIX, EMERGENCY RESET BUTTON & PULL CORDS BY OTHERS.
- 3. REFER TO DRG. No. 200 FOR ELEVATIONS.
- 4. REFER TO DRG, No. 300 FOR SETTING OUT OF PLUMBING, ELECTRICAL, & WASTE INLET & OUTLET POSITIONS.
- 5. CHANGING PLACES DOORWAY:
  CLEAR OPENING WHEN DOOR IS
  FULLY OPEN TO MEASURE 1000mm
  MINIMUM TO CONFORM WITH
  BS8300
- CLEAR OPENING DIMENSION SHOULD ACCOUNT FOR INTERNAL GRAB RAIL PROJECTION.
- DOOR OPENINGS THAT LEAD TO THE CHANGING PLACES TO BE 1000mm MINIMUM.

## 6. PATRESSING:

ENSURE 25mm MINIMUM PLY
PATRESSING IS INSTALLED TO PROVIDE
ADEQUATE SUPPORT FOR FIXING
EQUIPMENT.

• MDF OR OSB IS NOT ACCEPTABLE AS AN ALTERNATIVE.

INDICATES WHERE PLY
PATTRESSING IS REQUIRED
BEHIND FINAL WALL FINISH

Р1	FIRST ISSUE		14.01.25
REV:	DESCRIPTION:	BY:	DATE:
ST	<sup>atus:</sup> PRELIMINARY ISSU	E	



113 Hopewell Drive Chatham, ME5 7NP Tel: 01634 949988 www.carespaces.co.uk

SITE:

TRENTABANK CENTRE

CHANGING PLACES
OPTION 2

SCALE AT A3:	DATE:	DRAWN:	CHECKED:	
1:30	13.01.25	M.J.	B.C.	
PROJECT NO:	DRAWING NO:		REVISION:	_
T.B.C.	T.B.C. 110		P1	

CHANGING PLACES
OPTION 2
12m²

SCALE 1:30